

REFURBISHMENT OF COUNTRY OFFICE CONFERENCE ROOM AND RECEPTION

ITEM	DESCRIPTION	QTY	UNIT	RATE GH¢	AMOUNT GH¢
	PAINTING Prepare and apply three coats of acrylic emulsion paint				
A	Internal walls	50	m ²		
B	Soffits of ceiling	60	m ²		
	GLASS WINDOWS Provide and install 10mm thick framed in aluminium window fixed to wall complete with accessories (1800mm x 2100mm)				
C		5	No		
	CEILINGS Provide and install suspended POP/ acoustic ceiling complete accessories				
D		60	m ²		
E	Provide recess light complete in POP ceiling with all accessories	10	No		
	MAIN RECEPTION Cladding of electrical panels on wall and finish completely	-	Item		
	Repaint entire area completely	-	Item		
	TILE, SLAB OR BLOCK FINISHING 600 x 600 x 10mm porcelain floor tiles laid on floated bed with kerabond tile adhesive.				
F		55	m ²		
	BEDS AND BACKING Cement and sand (1:3) as described in:				
H	38mm thick screeded backing	40			
I	12mm thick screeded backing	45			
	TOTAL FOR CONFERENCE ROOM & RECEPTION AREA REFURBISHMENT			GH¢	-

US\$

-